



www.terrtor.com

Skidster Plus Crew™

Construction: 1/8 inch diamond plate throughout.

Dry Weight: Approx 240 lbs

Dimensions: 48"W x 35"L

Installation: Uses factory bed mounting on the frame. Bolts provided.



Storage
Recessed flat fire hose rack.



Standard
Removable tool crib. Stokes basket platform



Tank
70 gallon (water) tank with internal baffles, center sloped bottom, vented

Pump
Davey 2 stage pump



Pump Engine
Honda 5.5 HP 4 Stroke



Hose Reel
Heavy duty Reelcraft® 1,000 PSI for 175 ft 3/4" hose. (hose optional)



Option #1
Scotty "Around the Pump"
Foam Injector



Option #2
2 gal stainless steel foam tank



Toll Free: 877.404.2288

Phone: 608.967.2288
terrtor@terrtor.com

2110 Long Valley Road
Hollandale, WI 53544

No modifications are made to vehicles for installation. We can also engineer and fabricate to your specifications. Images featured on this web site, specification sheets, and other documents are those of real, in-use units.

All rights reserved TerraTor Corporation 2017